




PLAN OF CULVERT SLAB & APRON SLAB
1:100




SECTION A-A
1:100




ELEVATION B-B
1:100




DETAIL 1
1:15




DETAIL 2
1:15




SECTION C-C
1:100




SECTION D-D
1:50




TYPICAL DRAINAGE SECTION
1:25



DETAIL OF EXPANSION JOINT IN BASE/ APRON SLAB
NTS



DETAIL OF MOVEMENT JOINT IN BARREL
WALLS AND ROOF SLAB
1:50



DETAIL OF EXPANSION JOINT BETWEEN
BARREL WALLS AND WINGWALL
1:50

CONCRETE NOTES

- ALL CONCRETE SHALL CONFORM TO THE REQUIREMENTS OF THE LATEST EDITION OF SANS 2001 CC1.
- THE TYPE AND ORIGIN OF AGGREGATE AND CEMENT SHALL BE SUBMITTED TO THE ENGINEER FOR COMMENT PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A MIX DESIGN AND REPORT BY A RECOGNISED CONCRETE LABORATORY, TO INDICATE THAT SUITABLE MATERIALS AND MIX PROPORTIONS WILL BE USED TO MAINTAIN WORKABILITY AND TO AVOID ALKALI AGGREGATE REACTION AND EXCESSIVE BLEEDING.
- MIX DESIGNS MUST BE SUBMITTED THOROUGHLY FOR APPROVAL BY THE ENGINEER BEFORE CONSTRUCTION COMMENCES. IT REMAINS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE MIX DESIGNS APPROVED BY THE ENGINEER.
- ALL SURFACES OF FOUNDATIONS UPON OR AGAINST WHICH CONCRETE IS TO BE PLACED SHALL BE FREE FROM STANDING WATER, MUD, LOOSE ROCK AND OTHER DEBRIS.
- CONCRETE CLASSES AND YOUNG'S MODULUS

DESCRIPTION	CLASS	E-MODULUS
MASS CONCRETE	15/30	-
BLINDING LAYERS	15/19	-
WINGWALLS & SLABS	W30/19	31 GPa
- CONCRETE STRENGTH SPECIFICATIONS

POSITION	MPA (28 DAYS)	STONE (MM)
FOUNDATIONS	30	19
BEAMS	30	19
SLABS	30	19
WALLS	30	19
- NO PUMPING OF CONCRETE SHALL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER. THEATER CONTRACTOR SHALL THOROUGHLY COMPACT ALL CONCRETE IMMEDIATELY AFTER IT HAS BEEN PLACED IN POSITION WITH THE AID OF EITHER APPROVED IMMERSION VIBRATIONS AND VIBRATING SHUTTERS FOR THIN SECTIONS, TOGETHER WITH RODS, SPATULAS, SHOVELS, ETC. IF NECESSARY.
- ALL CONCRETE SHALL BE CONTINUOUSLY CURED FOR 7 DAYS BY AN APPROVED METHOD - TO BE SUBMITTED TO THE ENGINEER.
- THE POSITION AND METHOD OF FORMING OF ALL CONSTRUCTION JOINTS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION.
- 75mm BLINDING LAYER CONCRETE TO BE CAST UNDER ALL REINFORCED SLABS AND CUT-OFF WALLS.
- CONCRETE COVER TO ALL STRUCTURAL REINFORCEMENT IS 50mm.
- SURFACE FINISHES

TYPE OF SURFACE	FORMED SURFACES	UNFORMED
-UNEXPOSED	CLASS F1	CLASS U1
-EXPOSED TO VIEW	CLASS F2	CLASS U2
-TOP OF INVERT & APRON SLAB	N/A	CLASS U2
- GENERALLY, THREE (3) CONCRETE TEST CUBES SHALL BE TESTED AT 7 DAYS AND A FURTHER 3 AT 28 DAYS. THE RESULTS SHALL BE IMMEDIATELY SUBMITTED TO THE ENGINEER. ONE SET OF TEST CUBES HAS TO BE MADE PER MIX OF CONCRETE OR PART THEREOF OF EVERY ELEMENT CAST.
- REMOVAL OF FORMWORK IN NORMAL TO HOT CONDITIONS TO BE APPROVED BY ENGINEER.
- MIX DESIGNS SHALL HAVE A MINIMUM CEMENT CONTENT OF 300kg/m³.
- NO OPENING, SLEEVES OR PIPES OTHER THAN AS SHOWN ON THE DRAWINGS SHALL BE CAST INTO THE STRUCTURE WITHOUT THE ENGINEER'S APPROVAL AND NO CUTTING FOR ANY REASON AT A LATER STAGE SHALL BE ALLOWED.
- THE CONTRACTOR SHALL ENSURE THE REINFORCEMENT REMAINS IN THE CORRECT POSITION DURING CASTING.
- ALL EXPOSED CONCRETE SHARP EDGES SHALL HAVE 25x25mm CHAMFERED CORNERS.
- ONLY CEM 1 (PO) CEMENT MAY BE USED IN ALL CONCRETE UNLESS THE ENGINEER GIVES WRITTEN APPROVAL OF A MIX CONTAINING OTHER TYPES OF CEMENT.

DRAWING SCHEDULE	
DRAWING No.	DESCRIPTION
ROMH-042-07-04	GENERAL ARRANGEMENT
ROMH-042-07-05	CONCRETE DETAIL
ROMH-042-07-06	REINFORCEMENT DETAIL
ROMH-042-07-10	DETAIL SHEET 1
ROMH-042-07-11	DETAIL SHEET 2
ROMH-042-07-12	DETAIL SHEET 3

FOR TENDER

CLIENT:



54 Relief Street
Mokopane
0801

MOGALAKWENA MUNICIPALITY

Tel: (015) 491 9600
Fax: (015) 491 9608

PROJECT:

CONTRACT No. :
UPGRADING OF GRAVEL ROADS AND STORMWATER IN
MOORDKOPPIE CLUSTER AT MABUSELA AND MASOGE VILLAGES

DESIGN COORDINATOR APPROVAL:

SIGNATURE _____ DATE _____

PROJECT MANAGER APPROVAL:

SIGNATURE _____ DATE _____

CLIENT APPROVAL:

SIGNATURE _____ DATE _____

REV	DATE	DESCRIPTION	DRAWN
A	JUL 2020	ISSUED FOR TENDER PURPOSE ONLY	SQ

REVISIONS

DRAWN: S. QUZA	CHECKED: S. SITHOLE	DESIGNED: P. SEOPA
SCALES:	AS SHOWN	DATE: SEPTEMBER 2020
DRAWING TITLE:	CONCRETE LAYOUT AND DETAILS MABUSELA MAJOR CULVERT	
SIZE:	A0	PROJECT No.
REV No.	A	DRAWING No. ROMH-042-07- 10-05

CONSULTANTS:



ROMH HOUSE
WHITBY MANOR OFFICE PARK
167 14 ROAD, NOORDWYK
MIDRAND

Tel: (010) 035 1460
Email: info@romh.co.za
Web: www.romh.co.za